

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

UCID--20323

DE85 008879

Support Structures for Optical Components in the Laser Demonstration Facility

Milestone Report 4014 January 25, 1985

Prepared by:

R. C. Finucane

R. C. Finucane

Reviewed by:

M. L. Spaeth

M. L. Spaeth, Laser Isotope Separation
Deputy Program Leader

Reviewed by:

E. I. Moses

E. I. Moses, Laser Isotope Separation
Associate Program Leader

Approved by:

J. I. Davis

J. I. Davis, Laser Isotope Separation
Program Leader

LAWRENCE LIVERMORE NATIONAL LABORATORY
University of California · Livermore, California · 94550

MASTER

80000000

80000000

SUPPORT STRUCTURES FOR OPTICAL COMPONENTS
IN THE LASER DEMONSTRATION FACILITY

The laser system in the Laser Demonstration Facility is mounted on an array of 108 support columns. This milestone report describes the design, analyses, testing, fabrication, installation, and performance characteristics of these supports.

1. DESIGN

For manufacturing simplicity, all 108 supports have a similar design, with minor modifications depending on whether the structure supports a copper laser, a dye-laser component, or an optical component. Each support is a rectangular steel tube fabricated from half-inch ASTM A-36 steel plate and filled with concrete after erection. Supports are 22 ft high, 1.5 ft deep, and 4 or 5.2 ft wide (see Figs. 1 and 2).

The supports are arranged throughout the building as shown in Fig. 3. In the copper laser bay, the supports are 4 ft wide and arrayed on 8 ft centers, leaving 4 ft gaps for support columns of the mezzanine floor, for air conditioning ducts to the first floor, and for vertical utility risers to the copper lasers.

In the dye and optics corridors, the supports are closely spaced, forming walls of nearly continuous optical surfaces (Fig. 3a). Some supports were more widely spaced to leave room for columns to support the mezzanine. After these mezzanine columns were installed, the gaps between the widely spaced supports were bridged by half-inch steel plates, so that optics could be installed at any location along the wall.




Fig. 1. Optical support structure for copper lasers.




Fig. 2. Optical support structure for dye lasers.



Fig. 3. Typical arrangement of supports in the laser bay. The supports are bolted to a monolithic inertia-pad foundation.




Fig. 3a. Typical arrangement of supports in the dye and optics corridors. The wider spaces allowed later installation of support columns for the mezzanine floor.

2. SEISMIC RESPONSE

Because of the high value of the laser system, the optical support structures were designed to stringent seismic design criteria, satisfying both the 1982 Uniform Building Code and the LLNL 1000-year return-period Design Basis Earthquake. Two steps of analysis and design were required.¹

The first step was analysis and design as required by the Uniform Building Code 1982 Edition (UBC), with an additional seismic load factor of 1.5 on connections. The laser supports are classified as elements of a structure with a corresponding horizontal force factor of 0.3 g. The allowable stresses for this design step are consistent with the UBC.

The second design step required a dynamic analysis for the LLNL Design Basis Earthquake. This earthquake has a 0.5-g horizontal peak ground acceleration coupled with a 0.33-g vertical peak ground acceleration. A response spectrum defines the frequency content and accelerations of this earthquake. Since the dynamic stresses do not exceed the elastic limits of the respective materials, a damping value of 5% of critical damping was selected.

A steel shell with a composite concrete core was selected as the structural system. This would give the tall vertical cantilevers excellent rigidity, ample strength, and enough mass to be relatively insensitive to transient vibrations. An elastic design method, similar to the working stress design method, was used to proportion the laser support structures. For this load case, the allowable stresses were limited to 90% of the steel's yield strength and 70% of the concrete's ultimate strength.

3. MOUNTING DESIGN

Structurally, the supports are considered to be 22-ft cantilevered composite vertical columns supported by a 3-ft-thick isolated reinforced concrete pad. Each column is grouted in place at its base and bolted to the pad with 3-ft-long high-strength steel bolts epoxied into holes drilled into the concrete pad. The bolts are 1.25 in. diameter (nominal), full-thread, ASTM A-354 Grade BD, embedded 2 ft into a 2-in. diameter hole. An ultimate strength test program was carried out to measure the pullout capacity of the bolts.² (See Fig. 4). The ultimate load capacity of the bolts was found to be 145,000 lb each, providing a safety margin of 2:1 during the 1000-year return-period Design Basis Earthquake.

4. FABRICATION AND INSTALLATION

Conventional construction contractors, selected by competitive bid, fabricated and installed the supports and filled them with concrete. To minimize delivery time, the supports were fabricated at two separate industrial facilities. Standard welding construction tolerances were used ($\pm 1/4$ inch). Inspectors hired by LLNL rejected three supports during fabrication.

The structures were trucked to the site, unloaded, and set in place using a forklift and winch (Figs. 5 and 6). Three-foot-long threaded steel bolts were then installed into predrilled holes and epoxied in place. Following final alignment and inspection (Fig.7), grout was pumped beneath each support and allowed to cure. Each bolt was then stretched to 80,000 lbs tension, and the nut tightened to final preload of 70,000 lbs. Finally, each support was pumped full of concrete.



Fig. 4. Test program room where ultimate pullout stress of bolts was determined.
The nearest bolt pulled out at 145,000 lb.



Fig. 5. Winching the support to a vertical position.




Fig. 6. A support secured on a forklift for transporting to its final position.



Fig. 7. Final alignment and inspection.




Fig. 8. Typical measured frequency response at one support. The ordinate indicates the relative amplitude of vibration.

5. PERFORMANCE

The performance characteristics of the supports were determined by a modal analysis measurement program carried out after the supports were installed.³ This program identifies modes of vibration by making a series of frequency response measurements throughout the structure; analysis of these measurements then yields a complex eigenvalue and eigenvector for each mode of vibration. The complex eigenvalue contains the natural frequency and damping value of the mode and the complex eigenvector contains the amplitude and phase of the mode. This characterization provides a mode shape defined spatially over the entire support for each mode of vibration. The mode shapes along with their eigenvalues completely describe the dynamic properties of the support.

The laser supports have nine modes of vibration in a bandwidth of 0-500 Hz (see Fig. 8). There are four bending modes, four torsional modes, and one plate mode. Typical shapes are shown in Fig. 9-12. The torsional modes consistently exhibited lower damping levels than did the other modes, thus giving them greater amplification factors. The amplitude of the first bending mode is very small in comparison to that of other modes, as shown in Fig. 8.

Table 1 presents a summary of the first nine modes and their damping coefficients. Also shown on this table are the first three modes as determined by a finite element analysis performed during the design phase. Good agreement exists between the measured and predicted performance.

6. CONCLUSION

Following installation of the supports, the mezzanine floor and utility systems were completed as planned. Optical components were welded directly to the supports. Heavier components, such as the large dye amplifiers, were mounted to bolts epoxied into the concrete core of the supports. The supports were judged to be an effective and economical approach to mounting a large-scale laser system.




Fig. 9. Typical shape of support when vibrating at 46.4 Hz (second bending mode).




Fig. 10. Typical shape of support when vibrating at 66.38 Hz (first torsional mode).




Fig. 11. Typical shape of support when vibrating at 123.8 Hz (third bending mode).




Fig. 12. Typical shape of support when vibrating at 198.8 Hz (second torsional mode).

Table 1. Calculated and measured characteristics of the first nine vibration modes of the supports for optical components in the Laser Demonstration Facility.

Mode No.	Measured frequency (Hz)	Damping (%)	Mode shape	Computed frequency (Hz)
1	7.68	1.48	1st bending	7.64
2	46.40	1.09	2nd bending	46.18
3	66.38	0.48	1st torsion	60.07
4	123.80	1.32	3rd bending	
5	198.81	0.46	2nd torsion	
6	228.24	2.10	plate	
7	331.62	0.47	3rd torsion	
8	335.10	3.04	4th bending	
9	467.31	0.53	4th torsion	

REFERENCES

1. S. Y. Kim, Structural Calculations, Laser Demonstration Facility, Frederickson Engineering Report J-1492, August 15, 1984.
2. R. L. Schwein, SISL Laser Support Structures Test Program, TEI Consulting Engineers Report WR-82239, April 19, 1984.
3. D. Gustaveson, Dynamic Analysis of the Laser Support Structures, LLNL memo to R. Patterson, September 10, 1984.

INTERNAL DISTRIBUTION

R.E. Batzel	L-1	J.Z. Holtz	L-459
J.I. Davis	L-466	M.A. Johnson	L-464
J.L. Emmett	L-488	T. Kan	L-462
A.C. Haussmann	L-28	E.I. Moses	L-462
		B.R. Myers	L-468
R.D. Dewitt	L-372	R.W. O'Neil	L-462
		E.F. Oberst	L-440
T.W. Alger	L-462	Y. Oster	L-440
G. Armantrout	L-468	J.A. Paisner	L-464
E.R. Ault	L-463	R.W. Patterson	L-462
R.C. Bell	L-466	C.L. Pomernacki	L-443
H.L. Chen	L-468	R.S. Schechter	L-466
A.R. Clobes	L-462	T.A. Shepp	L-470
C.M. Cornell	L-468	R.W. Solarz	L-464
M. Day	L-466	M.L. Spaeth	L-467
J.W. Dubrin	L-466	R.C. Stern	L-459
J.T. Early	L-466	F.M. Strange	L-445
R.G. Finucane	L-462	J.R. Taylor	L-443
T.J. Gilmartin	L-467	R.J. Vetterlein	L-441
L.A. Hackel	L-470	A.C. Williams	L-468
R.P. Hackel	L-463	J.M. Yatabe	L-466
M.P. Hacker	L-470		
R.S. Hargrove	L-467	T.J. Gilmartin	L-467
J.G. Harri	L-470	Milestone File	
J.L. Held	L-470		
R.E. Hendrickson	L-466	J.I. Davis	L-466
D.P. Hendry	L-466	CLYA Files	(15)
F.J. Holcomb	L-466		
		TID	L-658 (15)

EXTERNAL DISTRIBUTION

Martin Marietta Energy Systems

A.S. Braden
D.F. Craig
J.P. Forester
C.E. Frye
R.L. Hoglund
C.C. Hopkins
T.J. Huxford
G.R. Jasny
K. Jarmolow
A.L. Lotts
O.W. McDonald
J.R. Merriman
G.E. Michaels
J.P. Moore
J.E. Owen
J.S. Rayside
J.E. Rushton
T.E. Smith
Martin Marietta
Energy Systems, Inc., K-25
Oak Ridge, TN (18)

Department of Energy

R.E. Dierlam
N. Haberman
J.K. Hancock (Project File)
J.R. Longenecker
J.J. McClure
S.E. Peske
W.M. Polansky
US DOE
Office of Uranium Enrichment
Washington, DC (7)

R.T. Bredderman
US DOE
San Francisco Operations Office
Oakland, CA

R.T. Ooten
US DOE
Oak Ridge Operations Office
Oak Ridge, TN

US DOE
Technical Information Center
Oak Ridge, TN (27)