CONF-900944--9

UCRL-JC-103596 PREPRINT

Палатира (+5 f) Ост о 4 1990

awtence re Livetingato

and orabot.

# FENIX, A Test Facility for ITER and Other New Superconducting Magnets

D. S. Slack **R. E. Patrick** J. R. Miller

This paper was prepared for submittal to the 1990 Applied Superconductivity Conference, Snowmass Village, Co, 9/24-28/90

September 21, 1990

This is a preprint of a paper intended for publication in a journal or proceedings. Since changes may be made before publication, this preprint is made available with the understanding that it will not be cited or reproduced without the permission of the author.

#### DISCLAIMER

This document was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor the University of California nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial products, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or the University of California. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or the University of California, and shall not be used for advertising or product endorsement purposes.

## FENIX, A TEST FACILITY FOR ITER AND OTHER NEW SUPERCONDUCTING MAGNETS

D.S. Slack, R.E. Patrick, and J.R. Miller Lawrence Livermore National Laboratory P.O. Box 5511, L-643 Livermore, CA 94550

# UCRL-JC--103596

#### DE91 000654

#### Abstract

The Fusion ENgineering International eXperimental (FENIX) Test Facility which is nearing completion at Lawrence Livermore National Laboratory, is a 76-t set of superconducting magnets housed in a 4-m-diameter cryostat. It represents a significant step toward meeting the testing needs for the development of superconductors appropriate for large-scale magnet applications such as the International Thermonuclear Experimental Reactor (ITER). The magnet set is configured to allow radial access to the 0.4-m-diameter high-field region where maximum fields up to 14 T will be provided. The facility is fitted with a thermally isolated test well with a port to the high-field region that allows insertion and removal of test conductors without disturbing the cryogenic environment of the magnets. It is expected that the facility will be made available to magnet developers internationally, and this paper discusses its general design features, its construction, and its capabilities.

This work was performed under the auspices of the U.S. Department of Energy by Lawrence Livermore National Laboratory under contract number W-7405-ENG-48.

#### Introduction

Lawrence Livermore National Laboratory (LLNL) is, with the support of the Department of Energy (DoE), constructing a new facility at LLNL to meet test specifications for the International Thermonuclear Experimental Reactor (ITER).

The Fusion ENgineering International EXperimental Magnet Facility (FENIX) is a significant step forward in meeting the testing requirements necessary for the development of superconductors for large-scale, superconducting magnets.

A 14-T, transverse field covers a test volume of  $150 \times 60 \times 150$  mm in length. Here conductors of the size to be used in ITER can be tested.

Proposed conductors for ITER measure ~35 mm on one side and will operate at currents of up to 40 kA at fields of ~14 T. The testing of conductors and associated components, such as joints, require large-bore, high-field magnet facilities; FENIX will be the only facility available that can match ITER conditions. Consequently, FENIX will be the gate way to the next phase of conductor development for ITER.

FENIX is being constructed using the existing  $A_{20}$ and  $A_{21}$  magnets from the idle MFTF (Mirror Fusion Test Facility). The east and west  $A_2$  pairs will be mounted together to form a split-pair solenoid. The pairs of magnets

uster i na

are now installed in a 4.0-m cryostat vessel located in the HFTF (High-Field Test Facility) building at LLNL. Each magnet is enclosed in its own cryostat, the existing 4.0-m vessel serving only as a vacuum chamber.

Figure 1 shows the two magnets being installed in FENIX. Figure 2 shows the second magnet being lowered into place in the four-meter vacuum vessel.



#### Figure 1. Magnets in Place

As previously used, the magnets developed fields of 12 T. A field of 14-T will be achieved in FENIX by using iron cores in the magnet bores and bringing the two magnet sets close together. A 60-mm gap between the magnet pairs permits insertion of conductors to be tested in the 14-T transverse field. The aluminum spacer plates that maintain this gap and the notch where test conductors are inserted can be seen in Fig. 2.

Forced-flow helium at adjustable temperatures, pressures, and flows will be provided to sample conductors being tested. Samples can be from one to several meters in length, with about 0.15 m being in the uniform, high-field region. Power supplies are available to provide currents up to 40 kA.

The cost of constructing FENIX is minimized by the use of pre-existing equipment. The cryogenic equipment, cryostat, magnet, and sample power supplies, are in place. The only major expense is the relocation and integration of the MFTF  $A_{20}$  and  $A_{21}$  magnets. The total cost for setup of a SPE THERE DOCE OF SETUP A SPECIFIC SETUP.

Manuscript received September 24, 1990.



Figure 2. Magnet Installation

FENIX is about \$1M. This compares favorably with an estimated cost of \$20M for construction of a comparable, all new facility.

Forced-flow helium at adjustable temperatures, pressures, and flows will be provided to sample conductors being tested. Samples can be from one to several meters in length, with about 0.15 m being in the uniform, high-field region. Power supplies are available to provide currents up to 40 kA.

The cost of constructing FENIX is minimized by the use of pre-existing equipment. The cryogenic equipment, cryostat, magnet, and sample power supplies, are in place. The only major expense is the relocation and integration of the MFTF  $A_{20}$  and  $A_{21}$  magnets. The total cost for setup of FENIX is about \$1M. This compares favorably with an estimated cost of \$20M for construction of a comparable, all new facility.

Work on FENIX is well underway with a target completion date of December 1990. As of August 1990 the magnets are installed and plumbing is completed in the 4-m vessel. Vacuum and cryogenic systems are being installed. The facility will be available for use by researchers internationally.

Services installed in FENIX to support the sample conductors are described in the following sections. Helium flows, temperature control, etc. provided are intended to satisfy most test programs. However, modifications to these services can be made if required.

#### General Description

Figure 3 shows a pictorial cutaway. The A<sub>2</sub> magnet sets were removed from the MFTF facility in June 1989. The various components (including magnet supports, helium reservoir, and test well) are installed. A Koch, model 2800, helium refrigerator is in place at the FENIX site



Figure 3. FENIX Magnet Facility

and will be used to provide refrigeration to the facility's A<sub>2</sub> magnet sets, their vapor-cooled supports, and current leads. An Airco 400-W helium refrigerator also exists at the test site. The Airco refrigerator will be used to provide liquid helium to the test well, thus providing refrigeration for the test conductor leads and the forced flow through the test conductor.

Figure 4 shows the test-well, magnetic-field plot at the magnet centerline, where the field is greatest. The plot is dimensioned so future users can determine field conditions for test conductors.



Figure 4. Magnetic Field Plot

Figure 5 shows the the existing building, crane, and 4-m cryostat. The dotted lines above the 4-m cryostat depict the test conductor and its supporting structure. The coldsink and heat-exchanger coils used to provide cryogens to the test conductor are within the upper dotted lines. The



Figure 5. Building Elevation

test conductor can be removed from the test well without warming the facility.

### Forced-Flow Heliur. Available For Test Conductor

Figure 6 shows a schematic of the system used to provide cryogens to the test conductor. The heat exchanger is a coiled tube-in-tube unit located in the upper part of the test well. The liquid-helium bath is maintained by the Airco refrigerator and supports both lead cooling and conductor forced-flow cooling. Room-temperature helium flows from high-pressure storage through the heat exchanger, where it is cooled to near liquid-helium temperature. It then passes through a cold-sink coil where it is cooled to the liquid-helium-bath temperature. The flow then branches into four paths which can be separately controlled. Temperature to each path can be controlled by the heaters shown, as well as the bypass valve that bypasses the cold sink. Flow rate to each path can be controlled by the flow meters and valving shown in the upper right on Fig. 6.

The use of four paths provides the user with flexibility. For example, three paths might be paralleled to provide high flow to the main test conductor, and the fourth path used to provide flow to a conductor joint. Another possibility is providing flow to two different test conductors at the same time, with the ability to monitor conditions in each conductor separately.

The heaters can be used to provide pulsed or steadystate heat to the test conductors. Longer term testing with warmer inlets will probably be accomplished by using the bypass value to avoid the heat load introduced by the heaters.

As shown, inlet and outlet temperatures, pressures, and flows to each path can be monitored. One limitation of the present design is that the same inlet pressure is provided to all paths. Pressure-dropping valves could be used to vary inlet pressures, but these are not planned unless users indicate a need for them.

The extended lip on the smaller test conductor portion of the well permits operating it dry. Here a slight amount of heat will be added at the bottom of the test well to boil off any helium spillover from the upper test well. Pool-boiling conductors can also be tested by flooding the entire test well.

#### Flow available for Test Conductors

Inlet pressure:

0.5 to 2.5 MPa, adjustable



- Test conductor
  Conductor test well
  Upper test well
  Heat exchanger
  Temp. sensors
  LHe bath in test well
  Bath boil-off return
  Flow meters
  Heaters
  Cold sink coll
  By pass valve
  Pressure taps
- 13. He at 300°K

	End	1990				
	Date	Aug	Sep	Oct	Nov	Dec
FENIX	12/14/90					
Project management	12/11/90					
Systems design	08/29/90					
Documentation	12/14/90					
Parts fab/buy (out of group)	10/11/90					
Vapor cooled lead tests	08/09/90	1		niiki (onni ii metokai). An yaan		
Install magnets & plumbing	09/13/90				1	
Clean & vacuum leak test	10/19/90	1				
Vacuum system	10/11/90	5 g (1)				
install thermal shielding	11/12/90	· ·				
Test well	11/13/90					
Cryogenics	11/16/90					-
Electrical systems	10/17/90					
Instruments/controls	11/08/90					
Mag. field shielding	10/19/90		0			
Assemble net sample/fixture	10/25/90					
install net sample	11/01/90					
Turn on/test/debug systems	12/14/90					
FENIX operational	12/14/90					



Inlet temperature: 3.5 K to >10 K — 3.5 K by pumping on test well, 4.3 K by use of atmospheric test well, higher temperatures using heaters and by-pass.

Flow rate:

Duty cycle:

30 g/s total for all paths with 0.5-MPa pressure at the test coil outlet. Maximum flow is proportional to pressure.

Continuous with 40-kA test conductors for several hours — here an existing 10-kL dewar will supplement the liquid-helium supply to the test conductor and its leads.

#### Test Conductor Power Supply, Controls, and Diagnostics

A NWL 6-V, 40-kA power supply is used as the test conductor current source. The voltage available to the sample at full current, 40 kA, is about 0.5 - 0.75 V. Watercooled leads are used to deliver the current from the power supply, located outside the building, to the sample in the FENIX test well. The power supply will be controlled by a Hewlett Packard 9000/300 series computer with userprogrammable ramping.

The diagnostics will consist of the following systems:

1. HP 9000/300 series computer at the FENIX/HFTF building with an EtherNet link to the LLL VAX 8600 on the NMFECC Network. Data will be archived on the LLL VAX in data files for the IDL data analysis/plotting software. We are planning to make the data available in WKS spreadsheet files, also for use in PC/MAC applications. This data can be available to the client/customer via the NMFECC network.

- 2. HP 3852 Data Acquisition Units with two multichannel, analog, sampling modules. One is a lowspeed (up to 20 samples/second with 20 channels available) Integrating DVM with high resolution and high accuracy. The second is a high-speed (up to 10,000 samples/second with 50 channels available), 13-bit, analog-to-digital converter.
- 3. Several miscellaneous signal conditioners are available for pressure transducers, strain gages, temperature sensors, hall probes, etc.

#### <u>Schedule</u>

Anticipated completion of the FENIX facility is about December 1990. Figure 7 is a project schedule.

#### **Acknowledgments**

This work was performed under the auspices of the U.S. Department of Energy by the Lawrence Livermore National Laboratory under Contract W-7405-Eng-48.

#### **References**

- 1. J. R. Miller, "The Use of Idle Equipment for ITER Magnet Development," Lawrence Livermore National Laboratory UCID-21453, 1988.
- J. P. Zbasnik et.al., "Construction and Operation of the 2. 12-T Superconducting Coils for the Mirror Fusion Test Facility," IEEE Trans on Magnetics, V. MAG-23, No. 2, 1987.
- T. A. Kozman et.al., "Construction and Testing of the 3. Mirror Fusion Test Facility Magnets," paper PH-1, IEEE Trans on Magnetics, V. MAG-23, No. 2, 1987.
- J. R. Van Sant and J. P. Zbasnik, "Liquid Helium Cooling of the MFTF Superconducting Magnets," paper LI-8, IEEE Trans on Magnetics, V. MAG-23, No. 2, 1987.



DATE FILMED

11/190

